

Addendum #1

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents and/or prior Addenda as noted below. All conditions, requirements, materials, and workmanship are to be as described in the Contract Documents unless specifically stated otherwise. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of (2) $8\frac{1}{2}$ x 11" sheets, (0) 11" x 17" sheets, and (0) 24" x 36" sheets.

Date	Owner Property Number	Owner Building Number	BHDA Project Number
Wed, 27 Jun 2018	516-2289	Provo UT North FM Group Building #45	1812
Project Designation		Project Address	
Franklin 2, Lakeside 2, 14 Restroom Remodel Provo UT West Stake		2530 West 200 South Provo, Utah	
Copies To			
	Church Project Manager Church Facilities Manager		
Bid Opening Time		Bid Opening Location	
Fri, 29 Jun 2018, at 2:00 pm		Temporary American Fork Project Management Office: Relief Society Room, LDS Meetinghouse 850 North 900 East American Fork, Utah	
1. Changes to Prior Ad	denda		
1.01. None.			
2. Changes to Procure	ment and Contracting Requirement	nts	
2.01. None.			
3. Changes to Specific	ations .		
3.01. None.			
4. Changes to Drawing	25		
4.01. Sheet A101 Demo	lition Plan, New Plan, and Interior E	levations	
piping locations or t	n: If the existing floor drain in Wom he new toilet partition locations, it	may be left in place.	e new plumbing fixture or

1. The floor drain shall not be allowed to be directly under a toilet partition support or panel.

4.02. Sheet M101 Mechanical Demolition Plans and New Plans

- A. Remove the Door Grille DG-1. No door grille is required.
- B. Plan 1 Enlarged Mechanical Demolition Plan and Plan 2 Enlarged Mechanical Plan: The existing exhaust duct and grille shown on these plans at Mother's 175 / Women 175 are not there. Install a new exhaust duct and grille in the location shown and run the duct out to a nearby soffit location. Install new prefinished soffit exhaust grille. Coordinate the location with the Architect. Repair the ceilings and soffit as necessary for this work.

2End of Addendum #1