



DFCM Addendum No. 1

Date: February 24, 2022

To: Contractors

From: Lucas Davis – DFCM Project Manager

Reference: White Rock Bay Campground – Antelope Island State Park
 Division of Parks and Recreation - Syracuse, Utah
 DFCM Project No. 22238510
 U3P Sourcing Event MW22048

Content: Total Addendum Page(s)
1

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to Disqualification.

1.1 SCHEDULE CHANGES: There are no Project Schedule changes within this addendum.

1.2 GENERAL ITEMS – Questions/Answers/Clarifications:

1.2.1 Question: Will there be adequate staging areas for storage containers being used to store materials purchased early, in an effort to avoid cost increases? Is there an approximate area dimension or number of storage containers "allowable" that we can confirm?

Answer: *A staging area near the jobsite will be provided for as many containers as needed for the project scope. It will be the contractor's responsibility to secure the staging area.*

1.2.2 Clarification - Item TS1 – Section 01 11 00 – Summary of Work. Add the following sentence to Section 1.16, paragraph A., under Section 01 11 00 “Summary of Work” in the project technical specifications: *Contractor will need to permit and coordinate with Syracuse City for construction water obtained at the fire hydrant by the entry gate when water is unavailable by the Marina during construction of project water system improvements. Contractor is responsible for any fees, hydrant meter, etc. required by Syracuse City.*

1.2.3 Clarification - Item D1 – Drawing Clarification: *Contractor to install “Carsonite”, or equal, blue water marker posts outside of roadway areas every ¼ mile on straight water main installation or at changes in direction.*

1.2.4 Clarification - Item D2 – Drawing Sheet C-500-1: *For Sanitary Sewer Manhole located at Sta: 41+09.61 (6.00 R) on drawing sheet C-500-11, the flow line invert labels for “In” and “Out” should be switched.*

- *FL (In-NW)=4310.83*
- *FL (Out-SE)=4310.73*